

14 PANEL SCREW – MINIMUM
ENGAGEMENT OF 1 1/2" INTO
STRUCTURAL SUPPORT –
SEE ENGINEERING DATA
FOR SPACING REQUIREMENTS

FOAM SEALANT –
CONTINUOUS BEAD

INTERIOR
DRYWALL

3" MINIMUM BEARING
AT EACH PANEL

NOTE: FLASH VALLEY WELL,
USING LONG SERVICE LIFE
MATERIAL

STRUCTURAL INSULATED PANEL
INSTALLATION GUIDE

TITLE ROOF VALLEY CONNECTION

PORTER
STRUCTURAL INSULATED PANELS

W. H. PORTER, INC. 4240 N. 136th AVE HOLLAND, MI 49424 (616) 399-1993
11/02

38-310